



DELHI POLICE PUBLIC SCHOOL

B-4, SAFDARJUNG ENCLAVE, NEW DELHI-110029

TELEPHONE NO.: 8130996770, 7683071791

www.delhipolicepublicschool.com, e-mail: dpps.school@gmail.com

Ref. No.: DPPS/ 38

Date : 14/3/23

M/S _____


Subject:- Corrigendum and Extension of date for submitting the bids for tender of Reconstruction of boundary wall along with the drainage system for Delhi Police Public School, Safdarjung Enclave, New Delhi.

Sir/Madam,

Sealed bids were called vide reference letter number DPPS/ 08, Dated 10.01.23 to Reconstruction of boundary wall along with the drainage system for Delhi police public School, Safdarjung Enclave, New Delhi-110029. In this regard the specifications of the required work is enclosed below.

Now the date of submitting the bids has been extended up to 28.03.2023 by 01:00 PM. Bids shall be opened on the same day at 01:30 PM.

All the terms and conditions will remain the same as mentioned vide reference above. In case the due date is declared a holiday, bid shall be opened on next working day at the given time. In case any vendor has submitted the bid and want to change the bid details, he may change the same fee/ EMD of the current bid shall hold good in such case. In case 2 bids are submitted by the bidder later bid shall be considered in all respect. The tender and other details are also available on school website (www.delhipolicepublicschool.com) for downloading.


Ruby Malhotra
(Head of School)



Abstract

S. No.	Description	Unit	Qty
1	Dismantling the existing concrete/ brickwork etc. and removal of all debris from site	Cum	19
2	Earth work in excavation over areas (exceeding 30 cm. in depth, 1.5 m in width as well as 10 sqm. on plan) including disposal of excavated earth, lift upto all depths disposed earth to be levelled and neatly dressed within the site. All Kinds of Soil	Cum	146
3	1:4:8 (1 Cement : 4 coarse sand (zone-III) derived from natural sources : 8 graded stone aggregate 40 mm nominal size derived from natural sources)	Cum	15
4	Providing & laying Thermo Mechanically Treated reinforcement bars for RCC work including cutting , straightening , bending, binding & placing in position complete at all heights and levels including cost of annealed binding wires.	Kg	1400
5	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level : 1:1.5:3 (1 cement : 1.5 coarse sand (zone-III) derived from natural sources : 3 graded stone aggregate 20 mm	Cum	14
6	1:2:4 (1 Cement : 2 coarse sand (zone-III) derived from natural sources : 4 graded stone aggregate 20 mm nominal size derived from natural sources)	Cum	6
7	Centering and shuttering including strutting, propping etc. and removal of form for		
a.	Foundations, footings, bases of columns, etc. for mass concrete	Sqm	29
b.	Lintels, beams, plinth beams, girders, bressumers and cantilevers	Sqm	49
c.	Columns, Pillars, Piers, Abutments, Posts and Struts	Sqm	41
8	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in: Cement mortar 1:6 (1 cement : 6 coarse sand)	Cum	37
9	a) 12 mm cement plaster of mix : 1:6 (1 cement: 6 coarse sand)	Sqm	82
	b) 15 mm cement plaster on rough side of single or half brick wall of mix: 1:6 (1 cement: 6 coarse sand)	Sqm	82
	c) 6 mm cement plaster of mix:1:6	sqm	90
	d) 18 mm cement plaster of mix:1:6 (1 cement:6 coarse sand) including floating coat of neat cement punning	sqm	201
10	MS support for concertina coil : Structural steel work in single section, fixed with or without connecting plate, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	Kg	240
11	Providing and fixing concertina coil fencing with punched tape concertina coil 600 mm dia	Meter	42