



DELHI POLICE PUBLIC SCHOOL

B-4, SAFDARJUNG ENCLAVE, NEW DELHI - 110029

TEL : 26177094 TELEFAX : 26187275

www.delhipolicepublicschool.com, e-mail: dppschoo@gmail.com

Ref. No: DPPS/ 48

Date : 21-01-2019

M/s _____

Subject: - Tender for laying down of new sewer line.

Sir,

Sealed bids are invited for laying down of new sewer line at DPPS/SJE as per sketch enclosed and dismantling the old exiting sewer line. The quotations should include cost of dismantling of old sewer line, disposal of waste(malba) such dismantled sewer at appropriate place(out of school), Laying down of new pipes with R.C.C material cover, digging of new manholes, etc and other miscellaneous and hidden works that required for passing the sewer drainage. The bidder will have to handover to the school such sewer off system or proper functional order well functions and storms sewer line in the bid price. No extra payment shall be made then the bids price.

The bids should reach the office by 28/01/2019 up to 2 PM. The bids will be open on same date at 3 PM. If the office happens to be closed on the last date, bid will be received and opened on the next working day at the same time.

The terms and conditions are as under:-

Eligibility of Bidder

1. The bidder must have PAN number and GST number with. A copy of PAN number and GST number must be enclosed with the quotation.
2. The bidder must be licensed plumber/Govt. contractor and should be given at least two reference where he has undertaken/ done similar.
3. Bidder should not be under a declaration of ineligibility/Black listed.


4. The validity of bids should be for 1 year and rates quoted shall remain unchanged till the completion of work. Any stoppage/disruption of work by any agency etc. shall be borne by the bidder himself.
5. The retention money (i.e. 10%) of tender will be forfeited, if the bidder withdraws during the period of work.
6. The retention money will be payable after the successful completion of defects liability period i.e. 1 year after the virtual completion of work.
7. The quotation will be rejected for the following reasons:-
 - (i) Quotations submitted after the given time and date.
 - (ii) Required documents like PAN number, GST no etc. not enclosed.
 - (iii) Earnest money of Rs- 25,000/ has to enclosed along with tender in form of DD.
 - (iv) Non production of original documents for verification, if asked for.
 - (v) Not found eligible as per requisite criteria.
8. The committee reserves the right to accept or reject any bid, and to annul the tender process and to reject all bids at any time without assigning any reason.
9. Conditional quotation shall not be accepted.
10. Bidder must agree to all terms and conditions of the bid.

Other terms and conditions

1. The contractor shall provide and maintain at his own cost proper sheds for storage and protection of all material i.e. pipes, manhole cover, Bricks, and any other equipment etc. required for such work.
2. Rates quoted by the Contractor shall remain same, till the stipulated completion period. Any increase in the cost of material/or labour during the progress of work either in the open market or coming into force by any fresh law by the Government or local authorities will not be payable to the contractor under any circumstances whatsoever except as provided in the contract.
3. The rates quoted by the contractor shall cover the cost (with all taxes) of all materials including loading, transportation to sites unloading, sorting under cover as required, labour etc.
4. Inspection from time to time shall be carried out by our Estate Officer and other officers of DPPS with the aim of keeping a check on specification/ quality of work being undertaken, by the contractor.
5. Any deviation required in lay out plan due to ground reality, shall be part of the contract and shall be carried out by the contractor. No extra payment is payable for such deviation.
6. All reasonable and proper precautions have to be taken by the contractor at all times during the progress of the work. The contractor shall be held entirely responsible for damages whatsoever, to the work and for labour hired by him for the required work, for any reasons.
7. An undertaking by the contractor along with bid is to be submitted to the effect that the contractor will undertake all precautionary measures prescribed and required for

such work and will be fully responsible for any miss-happening/accident etc. during the execution of said work and during warranty period.

8. The work must be completed within 30 days from the date of award of work. If the work is not completed within stipulated period, up to 10% of the cost of contract or 2% per week whichever is highest shall be forfeited at the time of final payment. Any penalty imposed by any concern agencies is also to be borne by the contractor.
9. In exceptional circumstances the principal DPPS and bidder may extend the validity of bid by mutual agreement.
10. The work awarded shall be given to the lowest bidder on the terms and conditions as decided by committee. Subject to satisfactory record of the vendor. However the committee reserve the right to award the contract to any bidder as deems fit.
11. The payment shall be done only after completion of work. No advance payment shall be made at any circumstance.
12. All rejected materials and other rubbish as it accumulates from time to time during the progress of work and completion shall be cleared and carted away by the contractor at his own cost and responsibility.
13. The contractor shall make necessary sanitary arrangements for the use of workers and keep them clean to the satisfaction of the local Public Health Authority. These shall be removed from the site on completion of the building and site leveled.
14. Any dispute is subject to the jurisdiction of Delhi Court only.
15. The electricity and water charge shall have to pay by the contractor if they utilized the same.
16. The existing manholes shall be fill up by the bidder and will have to dig and construct new manholes.
17. It shall be the sole responsibility of the bidder for any untoward incident or miss happening if any.


(Ruby Malhotra)
HOS

Scope of Work

S No	Description	Qty	Unit	Rate in Rs	Amount in Rs
1	Dismantling of road gully chamber of various sizes including cover with frame including stacking of useful materials near the site and disposal of unserviceable materials within 50 meters.	10	each		
2	Demolishing brick work manually/ by mechanical means and disposal of unserviceable material within 50 meters lead.				
	In cement mortar	4	cum		
3	Demolishing stone rubble masonry manually/ by mechanical means and disposal of unserviceable material within 50 meters lead :				
	In cement mortar	4	cum		
4	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 meters lead.				
	Nominal concrete 1:4:8 or leaner mix (i/c equivalent design mix)	185	Rmtr		
5	Dismantling stone slab flooring laid in cement mortar and disposal of unserviceable material within 50 meters lead.	60	sqm		
6	Disposal of building rubbish / malba / similar unserviceable, dismantled or waste materials by mechanical means, including loading, transporting, unloading to approved municipal dumping ground, beyond 50 m initial lead, for all leads including all lifts involved.	12	per trip		
7	Excavating trenches of required width for pipes, cables, etc including excavation for sockets, and dressing of sides, ramming of bottoms, depth up to 1.5 m, including getting out the excavated soil, and then returning the soil as required, in layers not exceeding 20 cm in depth, including				

	consolidating each deposited layer by ramming, watering, etc. and disposing of surplus excavated soil as directed, within a lead of 50 m :All kinds of soil				
	Pipes, cables etc. exceeding 80 mm dia. but not exceeding 300 mm dia	113	metre		
8	Clearing jungle including uprooting of rank vegetation, grass, brush wood, trees and saplings of girth up to 30 cm measured at a height of 1m above ground level and removal of rubbish up to a distance of 50 m outside the periphery of the area cleared.	100	sqm		
9	Clearing grass and removal of the rubbish up to a distance of 50 m outside the periphery of the area cleared.	100	sqm		
10	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :				
	1:4:8 (1 Cement : 4 coarse sand : 8 graded stone aggregate 20 mm nominal size)	5	cum		
11	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level :				
	1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size)	24	cum		
12	Centering and shuttering including strutting, propping etc. and removal of form for :				
	Beams, plinth beams,.. with water proof ply 12 mm thick	113	sqm		
13	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete up to plinth level.				
	Thermo-Mechanically Treated bars	750	kg		
15	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in:				

	Cement mortar 1:4 (1 cement : 4 coarse sand)	3	cum		
16	Making connection of drain or sewer line with existing manhole including breaking into and making good the walls, floors with cement concrete 1:2:4 mix (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size) cement plastered on both sides with cement mortar 1:3 (1 cement : 3 coarse sand), finished with a floating coat of neat cement and making necessary channels for the drain etc. complete :				
	For pipes 100 to 250 mm diameter	2	each		
17	Constructing brick masonry sewer chamber 120X60 cm depth up to 120 cm with bricks in cement mortar 1:4 (1 cement : 4 coarse sand) including 550x1110 mm pre-cast/cast in situ R.C.C. horizontal cover with frame complete as per standard design :				
	With common burnt clay F.P.S. (non modular) bricks of class designation 7.5 with channel and a floating coat of neat cement.	25	each		
18	Providing & laying of rigid PVC pipe as per IS specifications of various diameter including all fittings such as socket/collar/bend/tee with jointing with ist quality adhesive of approved make.				
	250 mm diameter /4 kg pressure, supreme	175	Mtr.		
	GST				